

## Fauldhouse Station Network Rail Station Improvement



Commercial Property Maintenance Services Ltd



Temporary platform construction



Platform wall removed and rebuilding commenced



Rebuilding of platforms complete

## PLATFORM PARTIAL RENEWAL TOP HALF

CPMS were awarded the contract by Network Rail to upgrade/refurbish Fauldhouse Station, West Lothian

The project comprised of the following elements:-

- Refurbishment of the both station platforms.
- Remove off-site the existing life expired over sail concrete blocks.
- Partial take down and rebuild top half of both platform walls
- Partial closing of both platforms.
- Remove and set aside existing copes for re-use.
- The installation of temporary non slip platform during the rebuilding process.
- Relay existing standard copes with new tactile slabs.
- Transition surfacing strips, varying in size from 500mm-3m
- Install copes to required stepping and gauge clearances.