

Ayr Station Hotel Network Rail Emergency Debris Removal



Commercial Property Maintenance Services Ltd



The dislodged debris was four stories above a busy operational platform.



Competent trained operatives utilised safety lines and abseil equipment to safely access the roof.



Once removed the actual size of the debris could be appreciated weighing in at nearly fifteen kilos.

DEBRIS REMOVAL OF DISLODGED RIDGE FROM STATION HOTEL'S ROOF.

CPMS were contacted by Network Rail via their help desk, to attend an Emergency response at Ayr Station to make safe loose debris on roof :-

- Within one hour CPMS had operatives on site, who were able to assess and confirm the position of the debris, install a safe system and barrier off the area below.
- CPMS liaised with Network Rail, Station and hotel staff to confirm that the debris required immediate removal due to the danger to the public.
- Within two hours of the call being received, a RAM S pack to facilitate the scaling of the hotel building, use of safety lines and abseil equipment had been submitted to Network Rail.
- Once confirmation to proceed had been received, operatives successfully scaled the building and removed the debris.
- 4 hrs from the initial call the platform was returned to normal operation, to the relief of the Station Manager.