

Fauldhouse Station Network Rail Station Improvement



Commercial Property Maintenance Services Ltd



Temporary platform construction



Platform wall removed and rebuilding commenced



Rebuilding of platforms complete

PLATFORM PARTIAL RENEWAL TOP HALF

CPMS were awarded the contract by Network Rail to upgrade/refurbish Fauldhouse Station, West Lothian

The project comprised of the following elements:-

- Refurbishment of the both station platforms.
- Remove off-site the existing life expired over sail concrete blocks.
- Partial take down and rebuild top half of both platform walls
- Partial closing of both platforms.
- Remove and set aside existing copes for re-use.
- The installation of temporary non slip platform during the rebuilding process.
- Relay existing standard copes with new tactile slabs.
- Transition surfacing strips, varying in size from 500mm-3m
- Install copes to required stepping and gauge clearances.