

Tulloch Station Network Rail New Platform wall



Commercial Property Maintenance Services Ltd



Old platform removed, new brick on old



New platform under construction ex services



New platform complete with existing services

PLATFORMS WORKS NEW PLATFORM WALL REMAINDER LEFT INTACT

CPMS were engaged by Network Rail to completely rebuild the Down platform at Tulloch on the picturesque West Highland line. The works were carried out without disruption to train services by utilising section D notices and undertaking the works in two halves.

The works included:-

- Demolish the existing platform wall
- New foundation
- New brickwork riser wall
- Pre cast oversail blocks
- Platform copes
- Drainage
- Platform infill and stone chip top dressing
- Stepping/Gauging clearance
- Possession management
- U-securit permit to work
- Safety critical staff
- WPP/ CPP
- All temporary works required for hand over / Hand back
- All works carried out on time and on budget with no issues